

**Roscommon County Road Commission
REQUEST QUOTE FOR
2017, HMA Base Crushing and Milling**

The Roscommon County Road Commission is requesting quotes for HMA Base Crushing with breakdown compaction with an approved roller, by the square yard, Cold-Milling HMA by the day to include mobilization and Trench Milling by the day to include mobilization. The RCRC will provide flag control when required. Quantities may vary. Quantities may include work on MDOT trunk lines. A “Certification of Insurance” is required to be on file prior to starting work within the right-of-way. **Quotes may be extended for additional years by agreement.**

HMA Base Crushing with Compaction

Crush existing HMA 2” into the existing aggregate base. Ensure 95 percent of the crushed material has a maximum particle size of 1 ½”, and the remaining 5 percent contains no particles larger than 4”. The RCRC will provide flag control and required support equipment (grader).

The approximate width of the existing HMA is 18 and 22 feet. The approximate depth of the existing HMA is 1 ½ to 2 ½ inches.

Approximate start date will be mid-July to mid-August.

Pay Item

HMA Base Crushing with Compaction..... Square Yard

Additional Mobilization to Roscommon Co..... Each

- Roscommon Township, Phase IV, A 25,445 Syd
- Eighth Street, Denton Township 800 Syd
- Dale & Channel Court, Markey Township 7885 Syd

Total HMA Base Crushing with Compaction, 34,130 Syd

