

Roscommon County CIPP Bid

- Can a unit based price, by the foot be used? **This would be the decision of the board, the bid is asking for a lump sum bid and that is what should be given.**
- Section 15-18 15" 52.9 Ft. Is this the correct footage? The map shows that it should be comparable to line 11-15 which is 253.8 Ft **This was a typo, the correct length is 279.5 feet.**
- Will pipe patches be an acceptable alternate to full length CIPP lining for the lines under 10ft? **No**
- Will water be available onsite from a hydrant? **No, water can be available from the Roscommon County Road Commission.**
- What facility nearby will take captured water from the lining process and will there be a cost for disposal? **Unsure, this will be the responsibility of the contractor.**
- Is there a dump site nearby for material removed from the sewer during cleaning? **The Road commission yard on Loxley Rd can be used.**
- Is traffic control to be included in the existing bid items or will there be another bid item added? **This should be included in the existing bid items.**
- At the location 45-Outflow, the outflow is covered over by a wooden structure that is overgrown with brush. Will the county be removing and replacing the covering for access to the end of the pipe? **The RCRC will make the outflow accessible.**
- Is steam an acceptable curing method? **Yes**
- Can the work completion date be pushed back 30 days? **Yes**
- Will a new bid tab be issued with the correction of the quantity for line 15-18? **No, please just strike through the incorrect quantity and write in the correct quantity on the bid tab.**